



MAHARASHTRA STATE WAREHOUSING CORPORATION
PUNE – 411037(www.mswarehousing.com)

CORRIGENDUM to e-Tender Notice No. 1/2022-2023 Sr. No.6

Corrigendum is hereby published with reference to the e-Tender Notice published on dt.12/04/2022, some changes have been made in BOQ, interested bidders may go through the CSD uploaded on “<http://mahatenders.gov.in>” (Organization name:- Co operation Marketing Textile Department, Mumbai) for the same.

Sr. No.	Reference to NIT and Page No. & Sr.No.	Existing	Modified
1.	Name of Work in BOQ	SUPPLY, INSTALLATION, TESTING, COMMISSIONING, STAMPING OF 60 MT CAPACITY PIT LESS TYPE ELECTRONIC LORRY WEIGHBRIDGES INCLUDING ELECTRICAL WORKS AT PADOLI, DIST. CHANDRAPUR.	SUPPLY, INSTALLATION, TESTING, COMMISSIONING, STAMPING OF 60 MT CAPACITY PIT LESS TYPE ELECTRONIC LORRY WEIGHBRIDGES INCLUDING ELECTRICAL WORKS AT PARBHANI MIDC, DIST. PARBHANI.

2	BOQ Item No. 2	<p>Supply, Installation and Commissioning in Lenovo 18.5-inch HD Monitor, TN Panel, (5ms Response time – 200 Nits Brightness – HDMI Cable Included - 72 % Color Gamut – TUV Blue Light Certification), LED Backlit. as per specifications enclosed completed including as directed.</p>	<p>Supply, Installation and Commissioning weighing indicator having 32 bit processor, processor clock 80Mhz, with various protection like spike suppressor for input transients, opto-isolation of signals etc. sigma delta type convertor with 24 bit resolution, conversion speed 25samples per second, with load cell excitation of 8VDC with current capability to drive upto 12 load cells of 350 ohms input resistance, display of 6-digit red, one inch height, 7 segment LED display for weight display & other parameters, with 4 key keypad of keyboard, showing indication buzzer for fault & data entry, isolated RS-232 serial port, USB serial port, Remote display port is provided to connect 8 inch height bright red LED display to indicate the weight on the platform alongwith selectable load cell sensitivity & auto zero tracking, inbuilt clock, mounting accessories etc. complete as directed by Engineer incharge.</p>
---	---------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



General Manager (Engg.)